

# **Addendum #1**

## **TOWN OF WAYLAND INVITATION FOR BIDS**

**#18-1063-IFB**

### **SUPPLY AND INSTALLATION OF VINYL FLOORING**

#### **AT WAYLAND MIDDLE SCHOOL**

**INCLUDING REMOVAL OF CARPET, TILE AND BASEBOARD PRIOR TO INSTALLATION**

**NOTE: Submission deadline remains unchanged, scheduled for Thursday, April 26, 2018 at 2:00 PM**

The Town of Wayland is issuing this addendum to provide clarification and answers to questions received during site visit of April 18, 2018.

#### Paragraph 1.14 Scope of Work

The project area includes all corridors and approximately half of each study hall area. The approximate area of the project is 25,885 SF this number is not exact and is offered only as rough guidance actual square footage area is the offeror's responsibility.

Transition pieces, VCT to existing flooring, shall be installed at each doorway leading off the corridors and at the dividing point in each study hall.

Pattern in the VCT shall be 2x2 alternating colors, three 2X2 color accent boxes every 12 linear feet.

Stairs shall also be included in the project. Steps shall be recovered with VCT and nosing, risers shall be covered with cove base. Exposed sides of stairs and ramps shall be painted.

The reading area in one study hall shall be re-carpeted using carpet squares and nosing on both the raised and sunken sections. Color and pattern shall be chosen from standard color palate.

Stairs and entrance at back of auditorium included in corridors.

Removal of equipment and furniture from corridors will be accomplished by owner.

Space on site will be made available for contractor supplied dumpster.

#### Floorplan

Incorrect square foot number removed.

Highlighting of corridor spaces improved.